



CFA PILING AT NANTWICH

Client:
Elan Homes



PROJECT DETAILS

CFA PILING

The project consists of drilling 171 no 300 o/d CFA piles to a max depth of 19mts below existing GL. The ground is made up of stiff silty sandy clay below approx 2mts of made ground, we also encountered bands of a red marl type soil. Drilling the max depth of 19mts was very tight. The rig used was our casagrande B125.

