

PALM PAPER KINGS LYNN

Installation of 3 HPPE Plastic 180mm diameter ducts

CLIENT
PALM PAPER

SIZE
180MM DIA

PROCESS
HORIZONTAL DIRECTIONAL DRILLING

The project comprised the installation of three separate 180mm electric ducts each 60m in length under a service road within a factory complex. Accuracy was essential to avoid drains, electric ducts and other closely installed services throughout the bores.

This was a tricky project. As one of the images shows, the drill head is just below an electric duct that the client had exposed. We would usually install these ducts as a trefoil (all three strapped together in one shot) but, due to the constrained working area, the solution was to install each duct separately.

