



CHURCH LANE, MARPLE

Temporary Works

MANSION HOUSE PROJECT
MANAGEMENT LTD

NUMBER OF PILES 64

CONTRACT NO. C21374

SPI Piling Ltd was employed to supply and for the installation of the following sacrificial temporary works for new housing/ flats development in Marple town centre.

Tosa installation (50t mobile crane)

64 nr GU16n @6.0m long (driven 5.5m)

All to form a temporary sacrificial retaining wall of overall length of 38.4 linear metres. 2 nr corners.

Temporary works are required to provide ground support at the site perimeter for excavation to formation level adjacent to the existing footpath and an existing building within 2 metres of the piling line.









