



## **A66 EDEN VALLEY PACKAGE**

A major programme of resurfacing providing a series of seven smoother journey resurfacing improvements along the A66 in Cumbria, a vital transport link for the North of England and Scotland

CLIENT HIGHWAYS ENGLAND VALUE **£1,210,000** 

CONTRACT NO. CP1000

What started off as seven separate Highways England schemes was, through collaborative Value Engineering, repackaged into one project across seven full weekend closures to minimise disruption and costs. Works undertaken included;

**Excavation** 

Kerbing

**Ironwork** 

Hardstandings

**Footways** 

Landscaping works

Watermain diversion for United Utilities

As Principal Contractor we co-ordinated Health and Safety of Highways England's Construction Works Framework community across the project, mitigating the effects of storm Callum and protecting finds from the Roman Era. Over 20,000 tonnes of asphalt was laid and 19,000 tonnes of planings removed on the first weekend using seven road planers, over 120 traffic management staff and four machine surfacing gangs. The project was carried out under Option C of the NEC suite of contracts.







