



PETERBOROUGH COMPRESSION STATION

Temporary Works

CLIENT COSTAINS GROUP PLC

CONTRACT NO. C21285

PROCESS
TEMPORARY WORKS

SPI Piling were awarded the contract to install a 150linm long sacrificial sheet piled retaining wall to enable Havercoft Construction Ltd to carry out a reduced level dig and construct a concrete retaining wall in front of the sheet piled wall.

The piles consist of 3m and 4m long GU8 sheet piles. There is a 1.2m long section of sheet pile wall that was required to have the sheet piles installed above the services. Havercroft marked out the location to ensure that the piles were not driven onto the existing pipe. Upon relocation of the services Havercroft pushed 2nr projecting the piles down to level.















